

Estimate excerpt

Every line shows quantity, rate, total, a stated range and the source it was measured from. Full deliverable: Excel in Unifomat, MasterFormat or your template.

REF	ITEM	QTY	UNIT	RATE	TOTAL	RANGE	CONF.	RATE BASIS	SOURCE
07 54 23	TPO roofing, 60 mil, fully adhered Incl. tapered insulation & flashings	18,400	SF	\$23.90	\$439,760	\$410k – \$470k	High	Unit rate, regional bids	Spec 07 54 23 §2.2 · A-501, A-502
08 44 13	Curtain wall, thermally broken RFI #7: head height at level 5 not dimensioned	6,900	SF	\$158.00	\$1,090,200	\$0.96M – \$1.22M	Low	Range until height confirmed	A-301 · Spec 08 44 13
08 71 00	Door hardware sets Per hardware schedule, 9 set types	146	EA	\$880	\$128,480	\$118k – \$139k	High	Set rate by type	Spec 08 71 00 · A-601 schedule
23 74 13	Packaged rooftop units, 25 ton Addendum 3: RTU-3 resized	4	EA	\$56,000	\$224,000	\$212k – \$236k	Medium	Supplier quotes (2)	M-401 schedule · Add. 3 item 12
02 41 19	Selective demolition, interior partitions Allowance pending existing-conditions survey	25,600	SF	\$1.85	\$47,360	\$38k – \$57k	Low	Allowance	D-101 note 4
Excerpt total					\$1,929,800	\$1.74M – \$2.12M			

Basis of estimate (excerpt)

- Rates: regional bid data, supplier quotes and past jobs, stated per line.
- Ranges reflect open items; they narrow as RFIs are answered.
- Lines not measured from a drawing (general conditions, escalation, contingency) state their basis instead of a sheet.
- Reviewed by an experienced cost professional before delivery; the reviewer is named in each proposal.

Findings report (excerpt)

- **Gap:** curtain wall head height at level 5 not dimensioned. A-301 · RFI #7
- **Gap:** no existing-conditions survey for interior demolition. D-101
- **Conflict:** spec calls for phenolic toilet partitions; finish schedule says HDPE. 10 21 13 · A-801 · RFI #8
- **Conflict:** hardware set 4 lists closers the door schedule omits. 08 71 00 · A-601 · RFI #9
- **Assumption:** RTU-3 priced at the Addendum 3 size. Add. 3